




Linea 2.9.10

LINEA RANGE
INTERIOR



Module : 600 mm





TECHNICAL CHARACTERISTICS

Panel dimensions	1880 x 600 mm
Cross-section of slats	20 mm (face) x 90 mm (height)
Spacing between slats	100 mm
Centre distance of slats	120 mm
Black rear counter-slats	34 x 45 mm
Overall thickness	117 mm
Wood species	Latted pine, latted oak
Surface mass (pine)	12 kg/m ²
Surface mass (oak)	14,3 kg/m ²
Openness percentage	83%

Rear surface : acoustic mineral wool tiles 2,4 kg/m² surfaced with black fleece facing (format 600 x 600 mm ; 20 or 22 mm thickness)
Not supplied by Laudescher

FITTING SYSTEM

Ceiling installation

To installed on T24 grid system
 or by screwing :
 – Selon NF EN 13964
 – Selon DTU 58-1

Wall installation

Mechanical fixing by screwing:
 – Selon DTU 36-2
 – Selon NF EN 14915

FINISH / REACTION TO FIRE (AS PER EN 13501-1)

Reaction to fire possibilities Euroclass B-s1,d0 or B-s2,d0 according to species and finishes.

ACOUSTIC RESULTS


The various data relating to acoustic absorption (α_p , α_w , absorption class) have been calculated according to ISO 11654 standard (LINEA + acoustic supplement).

CEILING INSTALLATION :

Linea 2.9.10 + LR 20mm on plenum E250mm

Acoustic absorption was measured as per the ISO 354 standard.

ACOUSTIC ABSORPTION COEFFICIENT



WEIGHTED INDEX :

$\alpha_w = 0,85$


ABSORPTION CLASS :

Class B

WALL INSTALLATION :

Linea 2.9.10 + LR 20mm on plenum E50mm

ACOUSTIC ABSORPTION COEFFICIENT



WEIGHTED INDEX :

$\alpha_w = 0,85$

ABSORPTION CLASS :

Class B